BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

Name of Work: Supply and installation of CCTV cameras at selected points with annual maintainance in ward no 11, Byatarayanapura.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	3.00	Outdoor PLZ IP Cameras with 20 X optical zoom with controller along with suitable mounting system (PTZ Pan Tilt and Zoom feature is availbale in this camera can be contolled by the software for pan Tilt and zoom feature at the contol center and can be programmed to view at different angles and zoom level continuosly. It operates at day and night and the viewing distance at clarity is about 100 metres	Nos	78462.00	Rupees Seventy Eight Thousand Four Hundred Sixty Two Only
2	18.00	Bracket (Corner Mount / Pole Mount/ Wall Mount) for mounting the PTZ camera.	Nos	4267.00	Rupees Four Thousand Two Hundred Sixty Seven Only
3	18.00	Outdoor 50 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 50 metres)	Nos	21160.00	Rupees Twenty One Thousand One Hundred Sixty Only
4	16.00	Bracket and weatherproof Installation kit for 50 Meter IP Camera	Nos	1545.00	Rupees One Thousand Five Hundred Forty Five Only
5	14.00	Outdoor 30 Meter IP Cameras with IR & Mounting Bracket (with IR for day and night vision and can provide a viewing distance of 30 metres)	Nos	15260.00	Rupees Fifteen Thousand Two Hundred Sixty Only
6	14.00	Bracket and weatherproof Installation kit for 30 Meter IP Camera	Nos	1491.00	Rupees One Thousand Four Hundred Ninety One Only
7	3.00	32 Channel NVR DS 7732 NI- E4 (with 4 Sata Option) the control box and the recording device to connect upto 32 devices, can be cascaded to provide additional cameras	Nos	66982.00	Rupees Sixty Six Thousand Nine Hundred Eighty Two Only
8	3.00	12 TB NAS Box for Back up (NET GEAR) provides storage for the recorded data for quick view back and storage	Nos	257420.00	Rupees Two Hundred Fifty Seven Thousand Four Hundred Twenty Only
9	5.00	4 TB SATA for storage and fitted in the NVR Device for storage	Nos	22850.00	Rupees Twenty Two Thousand Eight Hundred Fifty Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
10	18.00	A suitable sheet metal control panel to house site Equipments (Weather Proof) The power supply and the ethernet connectivity adaptor is stored in this box.	Nos	1526.00	Rupees One Thousand Five Hundred Twenty Six Only
11	18.00	Power supply for the camera.	Nos	461.00	Rupees Four Hundred Sixty One Only
12	18.00	Ethernet Switch for connectivity to Internet and Camera	Nos	950.00	Rupees Nine Hundred Fifty Only
13	20.00	Supply & Laying of Network and Power Cables from Camera to the control Box.	Nos	389.00	Rupees Three Hundred Eighty Nine Only
14	18.00	Video Manager Application Software for Display and Management of Camera on Video Display.	Nos	20000.00	Rupees Twenty Thousand Only
15	16.00	Installation, Erection & commissioning charges	Nos	5060.00	Rupees Five Thousand Sixty Only

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92
ಬೃ.ಬೆ.ಮ.ಪಾ., ಬೆಂಗಳೂರು

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))